


7383 Utica Blvd ~ Lowville, New York 13367 ~ 315-376-3333 ~ FAX 315-376-8139



Boulevard Properties, L.L.C.

Tuesday, June 27, 2006

Beth O'Donnell
Executive Director
Public Service Commission
211 Sower Boulevard
Frankfort, KY 40602-0615

RECEIVED

JUN 30 2006

PUBLIC SERVICE
COMMISSION

Dear Ms. O'Donnell,

Enclosed, please find one original and five copies of Shared Sites, LLC's application to construct a new Wireless Communications Facility at 1080 Old Highway 90, Monticello, Kentucky 42633. PSC Case #2006-00110.

Please contact me if anything is not in order.

Regards,



David B. Jantzi

FOR THE PUBLIC RECORD
COMMONWEALTH OF KENTUCKY
BEFORE THE PUBLIC SERVICE COMMISSION

IN THE MATTER OF:

APPLICATION OF SHARED SITES, LLC.)
AND AMERICAN CELLULAR CORPORATION)
FOR ISSUANCE OF A CERTIFICATE OF PUBLIC)
CONVIENCE AND NECESSITY TO CONSTRUCT)
A WIRELESS COMMUNICATIONS FACILITY AT)
1080 OLD HIGHWAY 90)
MONTICELLO, KENTUCKY 42633)
IN THE WIRELESS COMMUNICATIONS LICENSE AREA)
IN THE COMMONWEALTH OF KENTUCKY)
IN THE COUNTY OF WAYNE)

RECEIVED

JUN 30 2006

PUBLIC SERVICE
COMMISSION

SITE NAME: MONTICELLO NORTH
SITE NUMBER:

Shared Sites, LLC. As ultimate owner, and American Cellular Corporation, as a licensed public utility in the commonwealth of Kentucky, make this application.

The property on which the Wireless Communications Facility ("WCF") will be built is located at 1080 Old Highway 90, Monticello, Kentucky 42633. The WCF site is geographically positioned at 36-51-41.28 North latitude, 84-49-32.88 West longitude.

COMMONWEALTH OF KENTUCKY
BEFORE THE PUBLIC SERVICE COMMISSION

RECEIVED

JUN 30 2006

IN THE MATTER OF:

APPLICATION OF SHARED SITES, LLC.)
AND AMERICAN CELLULAR CORPORATION)
FOR ISSUANCE OF A CERTIFICATE OF PUBLIC)
CONVIENCE AND NECESSITY TO CONSTRUCT)
A WIRELESS COMMUNICATIONS FACILITY AT)
1080 OLD HIGHWAY 90)
MONTICELLO, KENTUCKY 42633)
IN THE WIRELESS COMMUNICATIONS LICENSE AREA)
IN THE COMMONWEALTH OF KENTUCKY)
IN THE COUNTY OF WAYNE)

PUBLIC SERVICE
COMMISSION

SITE NAME: MONTICELLO NORTH
SITE NUMBER:

UNIFORM APPLICATION: CONFIDENTIAL AND PROPRIETARY

Shared Sites, LLC. ("Shared Sites"), as ultimate owner, and American Cellular Corporation ("Provider") as a licensed public utility in the Commonwealth of Kentucky, hereinafter jointly referred to as "Applicants", respectfully submit their Application for a Certificate of Public Convenience and Necessity from the Public Service Commission to construct, maintain, and operate a Wireless Communications Facility ("WCF") to serve the customers of the Provider with wireless and telecommunications services, and other wireless service provider collocations in the area described herein.

In support of this Application, the Applicants respectfully provide and state the following information:

1. The complete names and addresses of the Applicants are:

Shared Sites, LLC., a Kentucky Limited Liability Company, having a mailing address of 1390 Chain Bridge Road #40, McLean, Virginia 22101 (703) 893-0806.

American Cellular Corporation, a Delaware Corporation, 3910 South Ave. Youngstown, OH 44512, 73134 having a local address of 124 South Keeneland Drive, Suite 1, Richmond, KY 40475, (606) 544-2355.

2. Shared Sites constructs, owns, manages, maintains, and operates independent communications networks. Shared Sites owns and manages safe, clean and well maintained facilities. Shared Sites facilities do not generate smoke, odors, noise, noxious gases, vibrations, or traffic increase. Shared Sites facilities will not pollute air, soil, or water, nor will they adversely affect radio or television reception or transmission. A certified copy of the Certificate of a Limited Liability Company issued by the Secretary of State of the State of West Virginia and a copy of the application for a Certificate of Authorization which was sent to the Secretary of State of the Commonwealth of Kentucky for Shared Sites, LLC. are attached or described as part of **Exhibit A**. A copy of the Certificate of Authorization issued by the Secretary of State of the Commonwealth of Kentucky and a copy of the Certificate of Merger issued by the Secretary of State of the State of Delaware for the Provider are attached or described as part of **Exhibit B**.

3. After completion of the proposed WCF, Shared Sites will lease or license space on said tower and the surrounding site so the Provider may locate and operate its facility including all required antennas and appurtenances. The proposed WCF will serve an area completely within the Provider's Federal Communications Commission ("FCC")

licensed service area in the Commonwealth of Kentucky. The Provider is authorized to provide wireless service by the FCC and the PSC. A copy of the Provider's FCC license to provide wireless service is attached to this Application or described as part of **Exhibit C**. Shared Sites has located the proposed site in a manner such that other wireless communications service providers will desire to collocate on said tower, and will endeavor to provide all necessary facilities to make collocation attractive to them.

4. The public convenience and necessity require the construction of the proposed WCF. The construction of the WCF will bring the Provider's services to an area currently not served or not adequately served by the Provider and will thereby enhance the public's access to innovative and competitive wireless telecommunications services. The WCF will provide a necessary link in the Provider's telecommunications network that is designed to meet the increasing demands for wireless services in Kentucky's wireless communications licensed area. The WCF is an integral link in the Provider's network design that must be in place to cover the proposed service area.

5. Shared Sites' construction of the described WCF is desirable because it allows for the collocation of additional wireless service providers within this portion of the Kentucky wireless communications licensed area. These services may include telecommunications, wireless data transfer and internet services, wireless cable, paging systems, 911 service, and other new products currently being developed in the wireless industry. In addition, the WCF will be available for use by governmental agencies and providers of emergency services. The WCF will provide a necessary link in Shared Sites' and the Provider's wireless infrastructure networks, and Shared Sites, as part of its business structure, will diligently pursue and encourage other wireless providers to collocate on the WCF. These services will provide increased competition in the in the local

Kentucky telecommunications market, which will, in turn, promote competitive pricing, quality, and coverage options to users of telecommunications services in this area. Shared Sites' vested interest in the collocation of wireless service providers promotes the same goals for the local consumers.

6. The Applicants propose to construct a WCF at 1080 Old Highway 90, Monticello, Kentucky 42633 (38-51-41.28 North latitude, 84-49-32.88 West longitude). In an area located entirely within the county referenced in the caption of this application. The property on which the WCF will be located is owned by Ronnie and Jenice Turner. The proposed WCF will consist of a 195 foot guyed tower with an approximately 4-foot lightning arrester attached to the top, for a total height of 199 feet. The WCF will also include concrete foundations to accommodate the placement of the Provider's proprietary radio electronics equipment. The equipment will be housed in a prefabricated cabinet or shelter that will contain: (i) the transmitting and receiving equipment required to connect the WCF with the Provider's users in Kentucky, (ii) telephone lines that will link the WCF with the Provider's other facilities, (iii) battery back-up that will allow the Provider to operate even after a loss of outside power, and (iv) all other necessary appurtenances. The Provider's equipment cabinet or shelter will be approved for use in the commonwealth of Kentucky by the relevant building inspector. The WCF compound will be fenced and all access gate(s) will be secured. A description of the manner in which the proposed WCF will be constructed is attached as **Exhibit D** and **Exhibit E**. Periodic inspections will be performed on the WCF in accordance with the applicable regulations or requirements of the PSC. The list of competing utilities, corporations, or persons is attached as **Exhibit F**.

7. Reduced copies of the site development plan have been included as **Exhibit D** and **Exhibit E** of this application. A vertical profile sketch of the WCF signed and sealed

by a professional engineer registered in Kentucky depicting the tower height, as well as a proposed configuration for the antennas of the provider and future antenna mounts, has also been included as part of **Exhibit E**. Foundation design plans and a description of the standards according to which the tower was designed signed and sealed by a professional engineer registered in Kentucky is included as part of **Exhibit D**.

8. The Applicants have considered the likely effects of the installation of the proposed WCF on nearby land uses and values and have concluded there is no more suitable location reasonably available from which adequate services can be provided, and that there are no reasonably available opportunities to collocate. The Applicants have attempted to collocate on suitable existing structures such as telecommunications towers or other suitable structures capable of supporting the Provider's facilities. No other suitable and available collocation site was found to be located in the vicinity of the site. Information regarding the Applicants' efforts to achieve collocation in the vicinity are presented as **Exhibit G**.

9. The Applicants have conducted a preliminary aeronautical evaluation for the proposed WCF. The evaluation determined that the proposed structure height at this site meets Federal Aviation Administration ("FAA") Regulation requirements. Furthermore, FAA notice is required for the proposed construction, and lighting or marking requirements may be applicable to this facility. A copy of the FAA Application is attached as **Exhibit H**. Upon receiving a "Determination" from the FAA, the Applicants will forward a copy as a supplement to this Application Proceeding

10. A copy of the Kentucky Airport Zoning Commission ("KAZC") Application for the proposed WCF is attached as **Exhibit I**. Upon receiving authorization from the KAZC,

the Applicants will forward a copy of the determination as a supplement to this Application Proceeding

11. The WCF will be registered with the FCC pursuant to applicable federal requirements. Appropriate required signage will be posted on this site upon receipt of the tower registration number.

12. A geotechnical-engineering firm has performed soil boring(s) and subsequent geotechnical-engineering studies at the WCF site under the supervision of a professional engineer registered in the Commonwealth of Kentucky who specializes in geotechnical engineering, including subsurface exploration. The geotechnical-engineering firm has performed many such studies for the communications industry. A copy of the geotechnical-engineering report and evaluation signed and sealed by a professional engineer registered in the Commonwealth of Kentucky who specializes in geotechnical engineering, including subsurface exploration, is attached as **Exhibit J**. The name and address of the geotechnical-engineering firm and the professional engineer registered in the Commonwealth of Kentucky who supervised the examination of this WCF site are included in **Exhibit J**.

13. Clear directions to the proposed WCF site from the County seat are attached as **Exhibit K**. The name and address of the preparer of **Exhibit K** is included in **Exhibit K**.

14. Shared Sites, pursuant to a written agreement, has acquired the right to use the WCF site and associated property rights. A copy of the agreement or an abbreviated agreement recorded with the County Clerk is attached as **Exhibit L**. Also included as part of **Exhibit L** is the portion of the full agreement demonstrating that in the case of abandonment a method is provided to dismantle and remove the cellular antenna tower .

15. Personnel directly responsible for the design and construction of the proposed WCF are well-qualified and experienced. World Tower Company, Inc. (the Tower Manufacturer) performed the tower and foundation design. The Tower Manufacturer is a nationally recognized manufacturer and designer of communication towers. The Tower Manufacturer has designed and installed communications towers throughout North America. The Tower Manufacturer has assigned S. M. Naeem Akhter, a professional engineer registered in the commonwealth of Kentucky to design the Tower for the WCF. This engineer specializes in the design and engineering of guyed, self support and monopole structures, and has extensive experience in the design and construction of projects similar to the Applicants'. These projects include the design of towers and the requires foundations of many other wireless facilities. All of the designs have been signed and sealed by S. M. Naeem Akhter. The construction of the proposed WCF will be performed by Shared Sites or their agents who are insured and experienced tower erection specialists. The Project Manager, David Jantzi, will manage the construction of the WCF and the tower erection. David has been erecting towers for the telecommunications industry for over 15 years. All tower designs will meet or exceed applicable laws and regulations.

16. Based on a review of Federal Emergency Management Agency Flood Insurance Rate Maps, the registered land surveyor has certified in **Exhibit M** that the proposed WCF is not located within any flood hazard area.

17. The possibility of high winds has been considered in the design of this tower. The tower has been designed and engineered by professional engineers using computer assistance and the same accepted codes and standards as are typically used for high-rise building construction. The tower has been designed to withstand a wind loading of 70

m.p.h. with ½ inch of radial ice. This tower has been designed in accordance with the Electronic Industries Association (“EIA”) 222-F 1996 Standards, which have been accepted and approved by ANSI and is a nationally recognized tower design standard. Similarly, the proposed WCF design has been developed with consideration of potential ground shaking based on a negligible seismic zone of 1. Seismic loading is regarded as secondary to the wind loading.

18. The site development plan signed and sealed by a professional engineer registered in Kentucky was prepared by David B. Sharp, and was designed from a survey performed by Mike McKinney. This site development plan is drawn to a scale of no less than one (1) inch equals 200 feet, and identifies every owner of real estate within 500 feet of the proposed tower (according to the Property Valuation Administrator) and is incorporated in the survey as part of **Exhibit E**. Every structure and every easement within 500 feet of the proposed tower or within 200 feet of the access road including intersection with the public street system is incorporated in the survey as part of **Exhibit E**.

19. Shared Sites, on behalf of itself and the Provider, has notified every person who owns property within 500 feet of the proposed tower by certified mail, return receipt requested, of the proposed construction. Each property owner has been informed of their right to request intervention. A list of the nearby property owners who received the notices, together with copies of the certified letters, are attached as **Exhibit N** and **Exhibit O**, respectively.

20. Shared Sites, on behalf of itself and the Provider, has notified the Wayne County Judge Executive and the City of Monticello Mayor by certified mail, return receipt requested, of the proposed construction. This notice informed the Wayne County Judge

Executive and the City of Monticello Mayor of his/her right to request intervention. A copy of this notice is attached as **Exhibit P**.

21. Two appropriate notice signs measuring at least two (2) feet in height and four (4) feet in width with all required language in letters of required height have been posted in a visible location on the proposed site and on the nearest public road and shall remain posted for at least two (2) weeks after filing of the Application. Copies of the postings are attached as **Exhibit Q**. The location of the proposed facility has been published in a newspaper of general circulation in the county where the WCF is located.

22. The property where WCF is proposed to be constructed is not zoned

23. The process that was used in selecting the site for the proposed WCF by the Applicants' radio frequency engineers was consistent with the process used for selecting generally all other existing and proposed WCF facilities within the proposed network design area. Before beginning the acquisition process, the Applicants carefully evaluated the location of the required WCF for possible collocation opportunities on existing structures. Radio Frequency Engineers used computer programs to evaluate the most effective coverage design for facilitating collocation potential on the proposed tower. Shared Sites and the Provider's radio frequency engineers have combined their efforts in order to develop a highly efficient network that is designed to serve the Federal Communications Commission licensed territory without extending beyond the Provider's approved boundary. The engineers selected the optimum vicinity in terms of elevation and location to provide the best quality service to customers in the service area. A proposed coverage area was considered by the Applicants when searching for sites that would provide both (i) the coverage deemed necessary by the Provider, and (ii) the coverage deemed necessary by Shared Sites to permit the integration of the proposed WCF into Shared Sites' overall

network design. No suitable towers or existing structures were found in the immediate area which would meet the technical requirements for this element of the telecommunications network. A map of the area in which the tower is proposed to be located which is drawn to scale and clearly depicts the necessary search area within which the site, pursuant to radio frequency requirements, be located is attached as **Exhibit R**.

24. A grid map showing the location of all existing cellular antenna towers that includes the general position of proposed construction sites for new cellular antenna towers within the Commission's jurisdiction and one-half mile outside the boundary of the planning unit's jurisdiction if that area contains either existing or proposed construction sites for cellular antenna towers is attached as **Exhibit S**.

25. All Exhibits to this application are hereby incorporated by reference as if fully set out as part of the Application.

26. All responses and requests associated with this Application may be directed

to:


David Jantzi
Boulevard Properties, LLC
7383 Utica Blvd.
Lowville, NY 13367
Telephone: (315) 523-6258

And

Kamal Doshi
Shared Sites, LLC
1390 Chain Bridge Road #40
McLean, VA 22101


Wherefore, the applicants respectfully request that the PSC accept the foregoing Application for filing and having met the requirements of KRS 278.020 and all applicable rules and regulations of the PSC, grant a Certificate of Public Convenience and Necessity to construct and operate the WCF at the location set forth herein for the respective networks in the commonwealth of Kentucky.

Respectfully submitted,



Kamal Doshi
Shared Sites, LLC
1390 Chain Bridge Road #40
McLean, Virginia 22101
Telephone: (703) 893-0806

And



Timothy J. Duffy
Chief Technical Officer / Senior Vice President
Network Operations & Engineering
American Cellular Corporation
14201 Wireless Way
Oklahoma City, OK 73134
(405) 529-8660

LIST OF EXHIBITS

- A. Certificate of LLC from the State of West Virginia and copy of application for Certificate of Authority to the State of Kentucky for Shared Sites, LLC.
- B. Certificate of Authorization from the State of Kentucky and Certificate of Merger for American Cellular Corporation
- C. Copy of FCC license for American Cellular Corporation
- D. Tower and Foundation Plan
- E. Site Development Plan:
 - Vicinity Map
 - Property Owner Listing
 - 500' Vicinity Map
 - Legal Descriptions
 - Site Plan
 - Vertical Tower Profile
- F. Competing Utilities, Corporations, or Persons List
- G. Collocation Report
- H. Application to FAA
- I. Application to Kentucky Airport Zoning Commission
- J. Geotechnical report
- K. Directions to WCF Site
- L. Copy of Real Estate Agreement
- M. Flood Plain Certification
- N. Notification Listing and Attorney Certification of Mailing
- O. Copy of Property Owner Notification
- P. Copy of County Judge Executive Notice
- Q. Copy of Posting Notices
- R. Copy of Radio Frequency Design Search Area
- S. Tower Map for Subject County

EXHIBIT A

CERTIFICATE OF LLC FROM THE STATE OF WEST VIRGINIA

AND

**CERTIFICATE OF AUTHORITY FROM THE COMMONWEALTH OF
KENTUCKY**

FOR SHARED SITES, LLC

State of West Virginia



Certificate

I, Betty Ireland, Secretary of State of the State of West Virginia, hereby certify that

SHARED SITES, LLC

Control Number: 82134

has filed its "Articles of Organization" in my office according to the provisions of West Virginia Code §§31B-2-203 and 206. I hereby declare the organization to be registered as a limited liability company from its effective date of January 13, 2006 until the expiration of the term or termination of the company.

Therefore, I hereby issue this

CERTIFICATE OF A LIMITED LIABILITY COMPANY



*Given under my hand and the
Great Seal of the State of
West Virginia on this day of
January 13, 2006*

Betty Ireland

Secretary of State

Commonwealth of Kentucky

Trey Grayson Secretary of State

Certificate of Authorization

I, Trey Grayson, Secretary of State of the Commonwealth of Kentucky, do hereby certify that according to the records in the Office of the Secretary of State,

SHARED SITES, LLC

, a limited liability company organized under the laws of the state of West Virginia, is authorized to transact business in the Commonwealth of Kentucky and received the authority to transact business in Kentucky on February 24, 2006.

I further certify that all fees and penalties owed to the Secretary of State have been paid; that an application for certificate of withdrawal has not been filed; and that the most recent annual report required by KRS 275.190 has been delivered to the Secretary of State.

IN WITNESS WHEREOF, I have hereunto set my hand and affixed my Official Seal at Frankfort, Kentucky, this 19th day of March, 2006.

Certificate Number: 28229

Jurisdiction: Shared Sites, LLC (Boulevard Properties)

Visit <http://apps.sos.ky.gov/business/obdb/certvalidate.aspx> to validate the authenticity of this certificate.





Trey Grayson
Secretary of State
Commonwealth of Kentucky
28229/0633042

EXHIBIT B

**CERTIFICATE OF AUTHORIZATION FROM THE
COMMONWEALTH OF KENTUCKY**

AND

CERTIFICATE OF MERGER FROM THE STATE OF DELAWARE

FOR AMERICAN CELLULAR CORPORATION

Commonwealth of Kentucky
Trey Grayson
Secretary of State

Certificate of Authorization

I, Trey Grayson, Secretary of State of the Commonwealth of Kentucky, do hereby certify that according to the records in the Office of the Secretary of State,

AMERICAN CELLULAR CORPORATION

, a corporation organized under the laws of the state of Delaware, is authorized to transact business in the Commonwealth of Kentucky, and received the authority to transact business in Kentucky on January 20, 2004.

I further certify that all fees and penalties owed to the Secretary of State have been paid; that an application for certificate of withdrawal has not been filed; and that the most recent annual report required by KRS 271B.16-220 has been delivered to the Secretary of State.


IN WITNESS WHEREOF, I have hereunto set my hand and affixed my Official Seal at Frankfort, Kentucky, this 13th day of February, 2006.

Certificate Number: 26879

Jurisdiction: Shared Sites, LLC

Visit <http://apps.sos.ky.gov/business/obdb/certvalidate.aspx> to validate the authenticity of this certificate.





Trey Grayson
Secretary of State
Commonwealth of Kentucky
26879/0576718

Delaware

PAGE 1


The First State

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF MERGER, WHICH MERGES:

"ACC OF KENTUCKY LLC", A DELAWARE LIMITED LIABILITY COMPANY, WITH AND INTO "AMERICAN CELLULAR CORPORATION" UNDER THE NAME OF "AMERICAN CELLULAR CORPORATION", A CORPORATION ORGANIZED AND EXISTING UNDER THE LAWS OF THE STATE OF DELAWARE, AS RECEIVED AND FILED IN THIS OFFICE THE THIRTY-FIRST DAY OF DECEMBER, A.D. 2003, AT 10:30 O'CLOCK A.M.

AND I DO HEREBY FURTHER CERTIFY THAT THE EFFECTIVE DATE OF THE AFORESAID CERTIFICATE OF MERGER IS THE THIRTY-FIRST DAY OF DECEMBER, A.D. 2003, AT 11:30 O'CLOCK A.M.

A FILED COPY OF THIS CERTIFICATE HAS BEEN FORWARDED TO THE NEW CASTLE COUNTY RECORDER OF DEEDS.



Harriet Smith Windsor
Harriet Smith Windsor, Secretary of State

2222565 8100M

AUTHENTICATION: 2856461

030845574

DATE: 01-07-04

EXHIBIT C

COPY OF FCC LICENSE FOR AMERICAN CELLULAR

Federal Communications Commission
Wireless Telecommunications Bureau
Radio Station Authorization

LICENSEE NAME: American Cellular Corporation

RONALD L. RIPLEY
AMERICAN CELLULAR CORPORATION
14201 WIRELESS WAY
OKLAHOMA CITY OK 73134

FCC Registration Number (FRN) 0003767324	
Call Sign KNKN556	File Number 0001571120
Radio Service CL - Cellular	
Market Number CMA447	Channel Block A
Sub-Market Designator 0	

Market Name Kentucky 5 - Barren

Grant Date 10-30-2001	Effective Date 01-07-2004	Expiration Date 10-01-2011	Five Yr Build-Out Date	Print Date 01-14-2004
--------------------------	------------------------------	-------------------------------	------------------------	--------------------------

SITE INFORMATION

Location	Latitude	Longitude	Ground Elevation (meters)	Structure Hgt to Tip (meters)	Antenna Structure Registration No.
2	037-18-06.0 N	085-55-41.0 W	285.1	78.9	1042214
Address	MUFORDVILLE SITE: 1 MI W				
City	County	State	Construction Deadline		
LEITCHFIELD	HART	KY			

Antenna: 1	Azimuth (from true north)	0	45	90	135	180	225	270	315
Antenna Height AAT(meters)		129.600	113.300	180.500	171.200	159.600	156.200	136.700	159.500
Transmitting ERP(watts)		75.900	100.000	91.200	100.000	75.900	31.600	24.300	31.600

Location	Latitude	Longitude	Ground Elevation (meters)	Structure Hgt to Tip (meters)	Antenna Structure Registration No.
5	036-44-13.0 N	085-42-10.0 W	309.7	88.1	1042225
Address	TOMPKINSVILLE SITE: 3151 EDMONTON ROAD				
City	County	State	Construction Deadline		
TOMPKINSVILLE	MONROE	KY			


Antenna: 1	Azimuth (from true north)	0	45	90	135	180	225	270	315
------------	---------------------------	---	----	----	-----	-----	-----	-----	-----

Conditions:

Pursuant to Section 309(h) of the Communications Act of 1934, as amended, 47 U.S.C. Section 309(h), this license is subject to the following conditions: This license shall not vest in the licensee any right to operate the station nor any right in the use of the frequencies designated in the license beyond the term thereof nor in any other manner than authorized herein. Neither the license nor the right granted thereunder shall be assigned or otherwise transferred in violation of the Communications Act of 1934, as amended. See 47 U.S.C. Section 310(d). This license is subject in terms to the right of use or control conferred by Section 706 of the Communications Act of 1934, as amended. See 47 U.S.C. Section 606.

EXHIBIT D

TOWER AND FOUNDATION DESIGN



TOWER ELEVATION

TITLE: 195' TYPE 36SR TOWER

WORLD TOWER

SCALE	NONE	DWN.	JCD	CKD.	10/18/04
FILE	DWG. NO.		Q04623		

ANTENNAS

ELEV.	DESCRIPTION	LINE	AZIMUTH
195'	(12) - CSS/SA 14-105 ON WD13X53	(12)- 1 5/8"	
180'	(12) - CSS/SA 14-105 ON WD13X53	(12)- 1 5/8"	
165'	(12) - CSS/SA 14-105 ON WD13X53	(12)- 1 5/8"	
150'	(12) - CSS/SA 14-105 ON WD13X53	(12)- 1 5/8"	
120'	(2) 4' SOLID DISHES	(2) - 1 5/8"	

MAXIMUM REACTIONS

BASE			ANCHOR		
SHEAR	.56	KIPS	RESULTANT	52.93	KIPS
COMPRESSION	83.43	KIPS	HORIZONTAL	38.83	KIPS
		KIPS	VERTICAL	36.11	KIPS

ELEV.	SIZE	BREAK STRENGTH	INITIAL TENSION	CUT LENGTH	SHACKLE	THIMBLE	TURN BUCKLE
180'	3/4 EHS	58300	5800	281'	1	3/4	1 1/4 X 24
140'	9/16 EHS	35000	3500	253'	3/4	3/4	1 X 18
70'	7/16 EHS	20800	2100	213'	---	1/2	3/4 X 12

GENERAL NOTES



1. TOWER IS DESIGNED TO SUPPORT THE GIVEN LOADS AND MEET THE PROVISIONS OF TIA/EIA-222-F FOR AN 85 MPH BASIC WIND SPEED WITH NO ICE AND IBC 2000.
2. ALL LINES MUST BE EVENLY DISTRIBUTED ON 3 TOWER FACES WITH A MAXIMUM OF 6 LINES EXPOSED TO THE WIND PER FACE.
3. WELDED CONNECTIONS SHALL CONFORM TO THE LATEST REVISION OF THE AMERICAN WELDING SOCIETY AWS.D 1.1.
4. TOWER AND ALL FABRICATED ACCESSORIES ARE HOT-DIP GALVANIZED IN ACCORDANCE WITH ASTM A123.
5. ALL BOLTS SHALL BE GALVANIZED ACCORDING TO THE STANDARD SPECIFICATION FOR ZINC COATING OF IRON AND STEEL HARDWARE ASTM A153.
6. LEG STEEL IS 50 KSI MIN. YIELD SOLID ROUND AND BRACING STEEL IS 36 KSI MIN. YIELD SOLID ROUND.
7. ALL STRUCTURAL BOLTS ARE ASTM A325.
8. GUY LENGTHS SHOWN ARE CHORD LENGTHS PLUS 30'.
9. TOWER SECTIONS ARE NUMBERED CONSECUTIVELY FROM BASE TO TOP.
10. TOWER SHOULD BE INSPECTED IN ACCORDANCE WITH TIA/EIA-222-F EVERY 3 YEARS
11. TOWER INSPECTION SHOULD ONLY BE PERFORMED BY EXPERIENCED QUALIFIED PERSONNEL. FOR ASSISTANCE IN PROPER MAINTENANCE OF YOUR TOWER, CALL WORLD TOWER @ 270-247-3642.

TITLE: 195' TYPE 36SR TOWER

WORLD TOWER

SCALE	NONE	DWN.	JCD	CKD.	WSE	DATE	10/18/04
FILE				DWG. NO.	Q04623T		

2.5 CU. YDS.
CONCRETE REQ'D.



GENERAL NOTES



1. CONCRETE TO HAVE 3000 PSI MIN. COMPRESSIVE STRENGTH AFTER 28 DAYS.
2. ALL REINFORCEMENT STEEL IS DEFORMED AND MEETS THE STRENGTH REQUIREMENTS OF ASTM A615 GRADE 60.
3. EMBEDDED STEEL TO HAVE 3" MIN. CONCRETE COVER.
4. FOUNDATION DESIGN IS BASED ON CUSTOMER SUPPLIED SOIL REPORT BY PACE GEOTECHNICAL, INC. PROJECT NO. 1772 DATED 10-15-2004.

REACTIONS		
SHEAR	.56	KIPS
DOWNLOAD	83.43	KIPS

TITLE: ANCHOR DETAILS
195' TYPE 36SR TOWER

WORLD TOWER

SCALE	NONE	DWN.	JCD	CKD.	<i>WDL</i>	DATE	10/20/2004
FILE				DWG. NO.	Q04623B		



GENERAL NOTES

1. CONCRETE TO HAVE 3000 PSI MIN. COMPRESSIVE STRENGTH AFTER 28 DAYS.
2. REINFORCEMENT STEEL IS DEFORMED AND MEETS THE REQUIREMENTS OF ASTM A615 GRADE 60.
3. CENTER LINE OF ANCHOR BEAM TO PASS THROUGH CENTROID OF BLOCK.
4. EMBEDDED STEEL TO HAVE A MIN. 3" COVER.
5. FOUNDATION DESIGN IS BASED ON CUSTOMER SUPPLIED SOIL DATA FROM PACE GEOTECHNICAL, INC. PROJECT NO. 1772 DATED 10/15/2004.

TITLE: ANCHOR DETAILS
195' TYPE 36SR TOWER

WORLD TOWER


SCALE	NONE	DWN.	JCD	CKD.	DATE
FILE				DWG. NO.	Q04623A

EXHIBIT E

SITE DEVELOPMENT PLAN

VICINITY MAP
PROPERTY OWNER LISTING
500' VICINITY MAP
LEGAL DESCRIPTIONS
SITE PLAN
VERTICAL TOWER PROFILE

PROPOSED WIRELESS COMMUNICATIONS FACILITY



MONTICELLO NORTH, KY
SHARED SITES, LLC
 1390 CHAIN BRIDGE ROAD #40, MCLEAN, VA 22101

UTILITY INFORMATION:

TELEPHONE SERVICE:

ALLTEL
 1-800-843-9214

ELECTRIC SERVICE:

SOUTH KENTUCKY RECC
 1-800-264-5112

HANDICAPPED REQUIREMENTS

FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. HANDICAPPED ACCESS NOT REQUIRED

PLUMBING REQUIREMENTS

FACILITY HAS NO PLUMBING

EXISTING PROJECT SITE SUMMARY

COUNTY:	WAYNE
SITE COORDINATES:	N 36° 51' 41.28" LAT. W 84° 49' 32.88" LONG.
ELEVATION:	990' AMSL
SITE ADDRESS:	1080 OLD HWY. 90 MONTICELLO, KY 42633
PROPERTY OWNER:	RONNIE & JENICE TURNER 701 N. MAIN STREET MONTICELLO, KY 42633
CONTACT NAME:	DAVE JANTZI 7383 UTICA BOULEVARD LOWVILLE, NY 13367
CONTACT TEL NO.:	315-523-6258
SITE NAME:	MONTICELLO NORTH

SHARED SITES, LLC

 REPRESENTATIVE SIGNATURE DATE

 OWNER APPROVAL DATE

 REPRESENTATIVE SIGNATURE DATE

DATE	DESCRIPTION	DRAWING INDEX
		TITLE SHEET
		C1 SURVEYED SITE PLAN
		C2 OVERALL SITE PLAN AND GENERAL NOTES
		C3 DETAILED SITE PLAN
		C4 SECTIONS
		C5 TOWER ELEVATION, ANTENNA PLAN & ANTENNA SCHEDULE
		F1 GENERAL FENCING DETAILS AND GENERAL NOTES
		S1 ICE BRIDGE AND FOUNDATION DETAILS & STRUCTURAL NOTES
		S2 STRUCTURAL FOUNDATION AND SLAB DETAILS
		E1 SINGLE LINE DIAGRAM AND ELECTRICAL NOTES
		E2 GROUNDING SITE PLAN AND GROUNDING RISER DIAGRAM
		E3 ELECTRICAL DETAILS

AMERICAN CELLULAR CORPORATION

CONTACT: RICHARD PENNINGTON
 1245 KEENELAND DRIVE
 RICHMOND, KY 40475
 OFFICE: (859) 544-5820
 FAX: (859) 544-5858

ANTENNA / TOWER


ENGINEERS / ARCHITECTS



Potesta & Associates, Inc.
 ENGINEERS AND ENVIRONMENTAL CONSULTANTS

125 Lakeview Drive, Morgantown, WY 26508
 TEL: (304) 226-2245 FAX: (304) 226-2246
 E-Mail Address: potesta@potesta.com

LOCATION MAP




USGS QUADRANGLE
 MONTICELLO, KY
 1"=4000'

DIRECTIONS :

FROM I-75 S TOWARD RICHMOND / KNOXVILLE (47.6 MILES), TAKE THE US-25 EXIT-EXIT 62- TOWARD KY-461 / RENFRO VALLEY / MT VERNON (0.2 MILES). MERGE ONTO US-25 TOWARD MT VERNON / KY 461 (0.7 MILES). STAY STRAIGHT TO GO ONTO KY-461 (17.9 MILES). TURN RIGHT ONTO KY-90 W / RUSSELL S DYCHIE MEMORIAL HWY. CONTINUE TO FOLLOW RUSSELL S DYCHIE MEMORIAL HWY. (8.7 MILES). TURN LEFT ONTO US-27 S. (7.0 MILES). TURN RIGHT ONTO KY-90. (4.2 MILES). TURN RIGHT ONTO HALLS LN. (<0.1 MILES) TURN LEFT ONTO LOOP RD. (<0.1 MILES).

PROJECT NAME: **MONTICELLO NORTH**
 MONTICELLO, KY 42633

DATE : 06/27/06



SCALE 1" = 138'

0 75 150 300

Drawn by Michael C. McKinney
 Instrument Person Michael C. McKinney
 Red Person Bonnie H. McKinney
 File McVynecou


Tower Site Below
 Monticello North

USGS 7.5' Quadrangle
 N80 01' (GDMS) 30-40-128
 Longitude: W 84-49-22.88
 Ground Elevation = 990'
 Geographic Information provided by:
 Shared Sites, L.L.C.

LEGEND

PLB Point of Beginning
 PL Property by
 O 1/2" x 1/2" or - 1/2" in
 3/4" x 1/2" or - 1/2" in
 3/4" x 1/2" or - 1/2" in

Monolithic North was observed in the field
 along 17' C 5916' from the PLB
 with reference bearing N 39° along a
 random base line on 06 / 02 / 06.



This survey is subject to any and all easements, restrictions
 and rights of way of record at the time.



Survey for Lease
Shared Sites, L.L.C.
 1390 Chain Bridge Road #40
 McLean, VA 22101
 Property Surveyed

Ronnie Turner
 791 North Main Street
 Monticello, Ky. 42633
 Deed Book 310 Page 467

Wayne County
 Commonwealth of Kentucky
 June 02, 2006

MCKINNEY LAND SURVEYING
 103 South Reed Street, Candia, Ky. 42728
 Phone 270 - 384 - 3293

DATE	DESCRIPTION
06/27/06	06-0035-014
06/27/06	
06/27/06	

MONTICELLO NORTH
 1080 OLD HWY 90
 MONTICELLO, KY 42633

SURVEYED SITE PLAN

REV.	DATE	DESCRIPTION

POTESTA

Potesta & Associates, Inc.
 ENGINEERS AND ENVIRONMENTAL CONSULTANTS

125 Lakeview Drive, Morgantown, WY 26508
 TEL: (304) 226-2246 FAX: (304) 226-2246
 E-Mail Address: potesta@potesta.com

MAGNETIC DECLINATION IS 4° 24'




Potesta & Associates, Inc.
 ENGINEERS AND ENVIRONMENTAL CONSULTANTS
 125 Lakeview Drive, Morgantown, WV 26508
 TEL: (304) 225-2246 FAX: (304) 225-2246
 E-Mail Address: potesta@potesta.com

REV.	DATE	DESCRIPTION


NO.	DATE	DESCRIPTION
06-0035-014	06/27/06	ADD NIS
06-0035-014	06/27/06	ISSUE FOR CONSTRUCTION

MONTICELLO NORTH
 1080 OLD HWY 90
 MONTICELLO, KY 42633

TOWER ELEVATION, ANTENNA PLAN & ANTENNA SCHEDULE




TOWER ELEVATION
 NIS




NOTE:
 ALL EXISTING CONDITIONS WITHIN FIELD VISIBLE FROM TO BE MAINTAINED UNLESS OTHERWISE NOTED BY CONTRACTOR.

NOTE:
 ALL EXISTING CONDITIONS WITHIN FIELD VISIBLE FROM TO BE MAINTAINED UNLESS OTHERWISE NOTED BY CONTRACTOR.



COAX ENTRY SCHEDULE
 NO SCALE

NOTE: COAX SCHEDULE MAY BE ADJUSTED IN THE FIELD FROM TO CONSTRUCTION. ALL COAX TYPES MUST BE IDENTIFIED WITH TAPE TO COLOR AND SIZE. ALL COAX TYPES MUST BE IDENTIFIED WITH TAPE TO COLOR AND SIZE.



COAX LAYOUT
 NIS

ANTENNA SCHEDULE

SECTION	A	B	C
ANTENNA	4'x4'	4'x4'	4'x4'
3RD CENTER (A.O.L.)	300'-0"	300'-0"	300'-0"
PERM. ANTENNAS PER SECTION	3	3	3
ANTENNA TYPE	PANEL	PANEL	PANEL
ANTENNA MFG.	SPECIAL	SPECIAL	SPECIAL
ANTENNA MODEL NO.	SC-4801-2H1	SC-4801-2H1	SC013-2H1
ANTENNA WEIGHT	5'	5'	5'
WINDLOADING	1-3/8" DIA.	1-3/8" DIA.	1-3/8" DIA.
ELECTRICAL CONNECTION			
INDX SIZE			

* VERIFY WITH SURVED BEFORE FROM CONSTRUCTION SHOULD BE IDENTIFIED IN FIELD FROM TO CONSTRUCTION.

ANTENNA COLOR CODING SCHEDULE

SECTION	A	B	C
ANTENNA 1	RED, RED, WHITE	BLUE, BLUE, WHITE/GREEN, GREEN, WHITE	RED, RED, WHITE
ANTENNA 2	RED, RED, WHITE	BLUE, BLUE, WHITE	GREEN, GREEN, WHITE
ANTENNA 3	RED, RED, WHITE	BLUE, BLUE, WHITE	GREEN, GREEN, WHITE
ANTENNA 4	GREEN, GREEN, WHITE	GREEN, GREEN, WHITE	GREEN, GREEN, WHITE

COLOR CODING
 NO SCALE

1. COLOR BAND ON WIRE LINE TO BE 1" WIDE WITH 1" SPACE LINE OF 3 WIRE'S
 2. COLOR BAND ON WIRE LINE TO BE 1" WIDE WITH 1" SPACE LINE OF 3 WIRE'S
 3. COLOR BAND ON WIRE LINE TO BE 1" WIDE WITH 1" SPACE LINE OF 3 WIRE'S
 4. SHAVE SECTION COLOR NEXT TO END CONNECTION

C5

GENERAL NOTES - ELECTRIC WORK

1. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE (NEC) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) 70B RECOMMENDATIONS FOR MAINTENANCE OF ELECTRICAL SYSTEMS.
2. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
3. ALL UNDERGROUND SERVICE SHALL BE IDENTIFIED BY THE CONTRACTOR PRIOR TO ANY WORK.
4. ALL SPARE CABLES SHALL BE LEFT WITH THE CONTRACTOR FOR FUTURE USE AND SHALL BE PROTECTED BY THE CONTRACTOR.
5. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
6. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
7. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
8. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
9. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
10. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
11. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
12. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
13. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.


SPECIAL CONTRACTOR NOTES

1. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
2. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
3. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
4. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
5. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.

1. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
2. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
3. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
4. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
5. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
6. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
7. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
8. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
9. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
10. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
11. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
12. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
13. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
14. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
15. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
16. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
17. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
18. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
19. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
20. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING SERVICE AND ALL ASSOCIATED EQUIPMENT AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.

NOTES:
1. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE (NEC) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) 70B RECOMMENDATIONS FOR MAINTENANCE OF ELECTRICAL SYSTEMS.

SINGLE LINE DIAGRAM
NO SCALE



REV.	DATE	DESCRIPTION


MONTICELLO NORTH
1080 OLD HWY 90
MONTICELLO, KY 42633

SINGLE LINE DIAGRAM
AND ELECTRICAL NOTES


DATE	BY	CHKD
06/27/20		
06/27/20		
06/27/20		

Potesta & Associates, Inc.
ENGINEERS AND ENVIRONMENTAL CONSULTANTS
125 Lakeview Drive, Morgantown, WV 26508
TEL: (304) 225-2246 FAX: (304) 225-2246
E-Mail: Address: potesta@potesta.com







GROUND BAR MOUNTING
SCALE: N. T. S.




H-FRAME (FRONT VIEW)
SCALE: N. T. S.



ELECTRICAL PEDESTAL
SCALE: N. T. S.



MASTER & TOWER GROUND BAR (MGB & TGB)
SCALE: N. T. S.




CONDUIT ENTRANCE DETAIL
SCALE: N. T. S.

- CONDUIT ENTRANCE NOTES:**
1. CONDUIT SHALL BE 5/4" DIA. (SEE SCHEDULE 40 D.A.V. (TYP. OF 2))
 2. GROUND SHIELD BE PLACED AS SHOWN FOR PROTECTIVE CONDUIT
 3. RESTRICTION TO CONDUIT SHALL BE AS SHOWN FOR 1/2" DIA. PVC TELCO CONDUIT
 4. CONDUIT SHALL BE INSTALLED ABOVE TOP OF PAD
 5. CONDUIT SHALL BE INSTALLED ABOVE PAD
 6. CONDUIT SHALL BE INSTALLED ABOVE PAD

NOTE:
CONTINUATION SHALL COORDINATE WITH ELECTRICAL CONTRACTOR FOR ALL CONDUIT INSTALLATION CONNECTIONS BY POWER CO.)

NOTE:
ALL TUBES SHALL BE FINISHED & INSTALLED BY ELECTRICAL CONTRACTOR (E.C.) UNLESS NOTED OTHERWISE.



H-FRAME (REAR VIEW)
SCALE: N. T. S.

REV.	DATE	DESCRIPTION


MONTICELLO NORTH
1080 OLD HWY 90
MONTICELLO, KY 42633

ELECTRICAL DETAILS

NO.	DATE
05-0035-014	09/27/05
05-0035-014	09/27/05
05-0035-014	09/27/05

Potesta & Associates, Inc.
ENGINEERS AND ENVIRONMENTAL CONSULTANTS
125 Lakeview Drive, Morgantown, WV 26508
TEL: (304) 226-2246 FAX: (304) 226-2246
E-Mail Address: potesta@potesta.com





NO.	REV.	DATE	DESCRIPTION
01		02/27/05	ISSUED FOR PERMITS
02		02/27/05	ISSUED FOR PERMITS
03		02/27/05	ISSUED FOR PERMITS
04		02/27/05	ISSUED FOR PERMITS

STRUCTURAL, FOUNDATION, & SLAB DETAILS
 MONTICELLO NORTH
 1080 OLD HWY 90
 MONTICELLO, KY 42633

NO.	REV.	DATE	DESCRIPTION

Potesta & Associates, Inc.
 ENGINEERS AND ENVIRONMENTAL CONSULTANTS
 125 Lakeside Drive, Morgantown, WV 26508
 TEL: (304) 225-2246 FAX: (304) 225-2246
 E-Mail Address: potesta@potesta.com



EXHIBIT F

COMPETING UTILITIES, CORPORATIONS, OR PERSONS LIST

COMPETING UTILITIES, CORPORATIONS, OR PERSONS LIST:

- American Towers
- Crown Communications
- SBA
- Verizon
- Cingular/AT&T
- Nextel
- T-Mobil
- Sprint
- Bluegrass Cellular
- Ramcell Cellular

EXHIBIT G
COLLOCATION REPORT

CellularONE

124 S. Keeneland Drive Richmond, KY 40475

859-544-4802
859-544-5858 FAX

Regional Rf Engineering Office
124 S. Keeneland Drive, Richmond, KY 40475

MONTICELLO NORTH

Discussion of site need and configuration

Currently, Cellularone's coverage along KY-90 and the business district growing west of KY-1275 along that route is not sufficient to provide solid service, especially in the commercial buildings there. The closest site south of Monticello is blocked by terrain known as Buster Hill. The distance, coupled with local terrain, blocks any meaningful signal from reaching the area.

The proposed site fills in the coverage problems noted above providing continuous service along KY-90 from west of our existing site near Frazer to near where KY-90 meets West Main Street from Monticello. The height is limited by FAA regulation in this area due to the Wayne County Airport.

Sincerely,

W. Eric Broviak
Regional Rf Engineering Manager

Cellular One

124 S. Keeneland Drive Richmond, KY 40475

859-544-4802
859-544-5858 FAX

Cellular One
124 S. Keeneland Drive
Richmond, KY 40475

April 11, 2006

To Whom it may Concern:

In regard to the proposed cellular communications site known as Monticello North, KY, this letter will seek to explain co-location issues.

To be able to serve the area, a structure in the realm of 250 ft. above ground level will be required. According to a survey by our site acquisition team, there simply are no tall structures in the area. Therefore, while it is the policy of *American Cellular* to pursue co-location opportunities wherever possible, there are no opportunities in this area. Thus, the construction of a new tower is the only alternative open to American Cellular.

Sincerely,

W. Eric Broviak
Regional Rf Engineering Manager

EXHIBIT H
APPLICATION TO FAA

Notice of Proposed Construction or Alteration (7460-1)

Project Name: SHARE-000042177-06 **Sponsor:** Shared Sites, L.L.C.

Details for Case : Monticello N. 2C

Show Project Summary

Case Status

ASN: 2006-ASO-3447-OE **Date Accepted:** 06/07/2006
Status: Accepted **Date Determined:**
Letters: None

Construction / Alteration Information

Notice Of: Construction
Duration: Permanent
if Temporary :Months: Days:

Work Schedule - Start: 08/01/2006
Work Schedule - End: 12/31/2006

State Filing:

Structure Summary

Structure Name: Monticello N. 2C
Structure Type: Antenna Tower
Other :
FCC Number:
Prior ASN: 2006-ASO-764-OE

Structure Details

Latitude: 36° 51' 41.28" N
Longitude: 84° 49' 32.88" W
Horizontal Datum: NAD83
Site Elevation (SE): 990 (nearest foot)
Structure Height (AGL): 199 (nearest foot)
Marking/Lighting: White-medium intensity

Other :

Nearest City: Monticello
Nearest State: Kentucky
Traverseway: No Traverseway

Description of Location: Old Highway 90
 Monticello, KY 42633
Description of Proposal: 195' wireless
 communications tower
 w/ 4' lightning rod
 facility located in fenced
 compound.

Common Frequency Bands

Low Freq	High Freq	Freq Unit	ERP	ERP Unit
806	824	MHz	500	W
824	849	MHz	500	W
851	866	MHz	500	W
869	894	MHz	500	W
896	901	MHz	500	W
901	902	MHz	7	W
930	931	MHz	3500	W
931	932	MHz	3500	W
932	932.5	MHz	17	dBW
935	940	MHz	1000	W
940	941	MHz	3500	W
1850	1910	MHz	1640	W
1930	1990	MHz	1640	W
2305	2310	MHz	2000	W
2345	2360	MHz	2000	W

Specific Frequencies

Close

EXHIBIT I

APPLICATION TO KENTUCKY AIRPORT ZONING COMMISSION



Kentucky Transportation Cabinet, Kentucky Airport Zoning Commission, 200 Mero Street, Frankfort, KY 40622		Kentucky Aeronautical Study Number	
APPLICATION FOR PERMIT TO CONSTRUCT OR ALTER A STRUCTURE INSTRUCTIONS INCLUDED			
1. APPLICANT -- Name, Address, Telephone, Fax, etc. Shared Sites, LLC- Kamal Doshi 1390 Chain Bridge Rd #40 Mclean, VA 22101 703-893-0806 (phone) 703-852-7289 (fax)		9. Latitude: <u>36</u> ° <u>51</u> ' <u>41</u> " <u>28</u> " 10. Longitude: <u>84</u> ° <u>49</u> ' <u>32</u> " <u>88</u> " 11. Datum: <input checked="" type="checkbox"/> NAD83 <input type="checkbox"/> NAD27 <input type="checkbox"/> Other 12. Nearest Kentucky City: <u>Monticello</u> County <u>Wayne</u>	
2. Representative of Applicant -- Name, Address, Telephone, Fax Boulevard Properties, LLC- Matt Wallack 7383 Utica Blvd Lowville, NY 13367 315-376-3333 (phone) 315-376-8139 (fax)		13. Nearest Kentucky public use or Military airport: <u>EKQ: Wayne County Airport</u> 14. Distance from #13 to Structure: <u>1.71 miles</u> 15. Direction from #13 to Structure: <u>WSW</u> 16. Site Elevation (AMSL): <u>990.00</u> Feet 17. Total Structure Height (AGL): <u>199.00</u> Feet 18. Overall Height (#16 + #17) (AMSL): <u>1,189.00</u> Feet 19. Previous FAA and/or Kentucky Aeronautical Study Number(s): 20. Description of Location: (Attach USGS 7.5 minute Quadrangle Map or an Airport layout Drawing with the precise site marked and any certified survey) <u>Old Highway 90</u> <u>Monticello, KY 42633</u>	
3. Application for: <input checked="" type="checkbox"/> New Construction <input type="checkbox"/> Alteration <input type="checkbox"/> Existing 4. Duration: <input checked="" type="checkbox"/> Permanent <input type="checkbox"/> Temporary (Months Days) 5. Work Schedule: Start <u>01 Aug 2006</u> End <u>31 Dec 2006</u> 6. Type: <input checked="" type="checkbox"/> Antenna Tower <input type="checkbox"/> Crane <input type="checkbox"/> Building <input type="checkbox"/> Power Line <input type="checkbox"/> Landfill <input type="checkbox"/> Water Tank <input type="checkbox"/> Other 7. Marking/Painting and/or Lighting Preferred: <input type="checkbox"/> Red Lights and Paint <input type="checkbox"/> Dual - Red & Medium Intensity White <input checked="" type="checkbox"/> White - Medium Intensity <input type="checkbox"/> Dual - Red & High Intensity White <input type="checkbox"/> White - High Intensity <input type="checkbox"/> Other 8. FAA Aeronautical Study Number _____			
21. Description of Proposal: <p>195' Wireless Communications Tower w/ 4' lightning rod facility located within fenced compound.</p>			
22. Has a "NOTICE OF CONSTRUCTION OR ALTERATION" (FAA Form 7460-1) been filed with the Federal Aviation Administration? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes, When <u>June 07, 2006</u>			
CERTIFICATION: I hereby certify that all the above statements made by me are true, complete and correct to the best of my knowledge and belief.			
<u>Matthew J. Wallack</u> Printed Name and Title		 Signature	
		<u>07 Jun 2006</u> Date	
PENALTIES: Persons failing to comply with Kentucky Revised Statutes (KRS 183.861 through 183.990) and Kentucky Administrative Regulations (602 KAR 050:Series) are liable for fines and/or imprisonment as set forth in KRS 183.990(3). Non-compliance with Federal Aviation Administration Regulations may result in further penalties.			
Commission Action: <input type="checkbox"/> Chairman, KAZC <input type="checkbox"/> Administrator, KAZC <input type="checkbox"/> Approved <input type="checkbox"/> Disapproved _____ Date _____			

EXHIBIT J
GEOTECHNICAL REPORT

**SUBSURFACE INVESTIGATION &
FOUNDATION RECOMMENDATIONS**

**PROPOSED MONTICELLO NORTH 2
CELL TOWER
MONTICELLO, KENTUCKY**

Prepared for:


**SHARED SITES, L.L.C.
C/O BOULEVARD PROPERTIES
LOWVILLE, NEW YORK**

Prepared by:

**ALT & WITZIG ENGINEERING, INC.
WEST CHESTER, OHIO**

MARCH 23, 2006

PROJECT NO. 06CN0072



Alt & Witzig Engineering, Inc.
6205 Schunacher Park Drive • Cincinnati, Ohio 45069
(513) 777-9890 • Fax (513) 777-9070

March 23, 2006

Shared Sites, L.L.C.
c/o Boulevard Properties
7383 Utica Blvd.
Lowville, New York 13367
ATTN: Mr. Matthew J. Wallack

RE: Subsurface Investigation &
Foundation Recommendations
Proposed Monticello North 2 Tower
Monticello, Kentucky
Alt & Witzig File: 06CN0072

Gentlemen:

In compliance with your request, we have completed a foundation investigation and evaluation for the above referenced project. It is our pleasure to transmit herewith three (3) copies of our report.

SITE LOCATION:

The site is located in Monticello, Kentucky. Specifically, this site is located at on Old S.R. 90. The general vicinity of the site is shown on the enclosed site location map in the appendix of this report.

The purpose of this subsurface investigation was to determine the various soils profile components, determine the engineering characteristics of the materials encountered, and provide information to be used in preparing foundation designs for the proposed communication tower.

Field Services

The field investigation included reconnaissance of the project site, drilling four (4) soil borings for the tower, performing standard penetration tests, and obtaining soil samples retained in the standard split-spoon sampler. The apparent groundwater level at the boring location was also determined.

The soil borings were performed with a conventional drilling rig equipped with a rotary head. Conventional hollow-stem augers were used to advance the holes. Representative samples were obtained employing split-spoon sampling procedures in accordance with ASTM Procedure D-1586.

During the sampling procedure, standard penetration tests were performed at regular intervals to obtain the standard penetration value of the soil. The standard penetration value is defined as the number of blows of a 140-pound hammer, falling thirty (30) inches, required to advance the split-spoon sampler one (1) foot into the soil. The results of the standard penetration tests indicate the relative density and comparative consistency of the soils, and thereby provide a basis for estimating the relative strength and compressibility of the soil profile components.

Laboratory Testing

The types of soils encountered in the borings were visually classified according to the Unified Soil Classification System and are described in detail on the boring logs. Representative samples of the soils encountered in the field were placed in sample jars and are now stored in our laboratory. Unless notified to the contrary, all samples will be disposed of after three (3) months.

Recommendations for Tower

Information provided by Boulevard Properties indicates that a 240 feet guyed cellular tower will be constructed at this site. It is anticipated that the structural loads of the tower will be supported by a conventional spread footings or drilled pier foundation.

Our borings encountered medium stiff and soft clay and silty clay to a depth of eight (8) to twenty-six (26) feet in the area of the tower. At this depth the borings encountered auger refusal on limestone and dolomite bedrock. A rock core was performed at boring location B-1 in the center of the tower from eleven (11) to twenty-one (21) feet below grade. The rock core indicated limestone to fissured dolomite. Recovery for the core was 47% for the first 5 feet and 22% for the bottom 5 feet. A Rock Quality Designation (RQD) of 0% was noted for both cores. This qualifies as poor quality bedrock.

The following soil parameters can be used to design a shallow foundation. Due to the seasonal variations in moisture content and freeze thaw cycles, no skin friction or resistance to passive pressure should be considered above four (4) feet.

B-1 and B-4						
Soil Description	Depth Below Existing Grade	Bearing Pressure (psf) SF=3	Dry Density (pcf)	ϕ	K_p	Coefficient of Friction Against Sliding
Clay	4' - 10'	3,000	110	10°	1.4	0.50
Limestone/Dolomite	10' +	6,000	125	35°	3.7	0.55

B-2						
Soil Description	Depth Below Existing Grade	Bearing Pressure (psf) SF=3	Dry Density (pcf)	ϕ	K_p	Coefficient of Friction Against Sliding
Clay	4' - 26'	2,000	115	20°	2.0	0.50
Limestone/Dolomite	26+'	6,000	125	35°	3.7	0.55

B-3						
Soil Description	Depth Below Existing Grade	Bearing Pressure (psf) SF=3	Dry Density (pcf)	ϕ	K_p	Coefficient of Friction Against Sliding
Clay	4' - 18'	3,000	115	20°	2.0	0.50
Limestone/Dolomite	18+'	6,000	125	35°	3.7	0.55

The weight of the backfill above the footings will be used to resist uplift forces; therefore, it is recommended that proper compaction techniques be maintained. Using approved granular material, it is recommended that a density of 100% maximum dry density in accordance with ASTM D-698 be achieved above the footings to finished grade.

Caissons/Drilled Piers

A caisson type foundation system can be used to support this structure. A caisson type foundation is advantageous to use when it is necessary to resist large overturning moments such as those caused by wind loads against the proposed structure. If caissons or drilled piers are used to support the structure, the following design parameters are recommended:

B-1 and B-4			
Depth Below Grade (Feet)	Allowable Skin Friction (psf) SF=2	Design End Bearing Pressure SF=3	Cohesion (Psf)
From ground surface to a depth of 4 feet below grade.	Negligible	---	Negligible
From 4 feet to 10 feet below grade.	500	3,000	500
At 9 feet below grade	1,000	6,000	1,000

Caissons should be no less than 30 inches in diameter.

B-2			
Depth Below Grade (Feet)	Allowable Skin Friction (psf) SF=2	Design End Bearing Pressure SF=3	Cohesion (Psf)
From ground surface to a depth of 4 feet below grade.	Negligible	---	Negligible
From 4 feet to 26 feet below grade.	300	2,000	250
At 26 feet below grade.	1,000	6,000	1,000

B-3			
Depth Below Grade (Feet)	Allowable Skin Friction (psf) SF=2	Design End Bearing Pressure SF=3	Cohesion (Psf)
From ground surface to a depth of 4 feet below grade.	Negligible	---	Negligible
From 4 feet to 18 feet below grade.	500	3,000	500
At 18 feet below grade.	1,000	6,000	1,000

All borings indicated dry conditions during and upon completion of operations. Concrete should not be dropped greater than five (5) feet through reinforcement steel. If caisson diameters do not allow for adequate fall distance from the reinforcement cage, a tremmie pipe would be required.

Our knowledge of this area indicates that rock shelves may be present at this site. Also, limestone floaters may be interbedded within the overburden clays above the sound rock layer. Therefore, prior to placement of concrete, all foundations placed on sound rock must be inspected by a representative of the soil engineer. This inspection is necessary to assure that each drilled pier designed to bear on sound rock, has extended below all floaters and into the sound limestone layer.

To substantiate the soundness of limestone, it is recommended that probe holes be drilled by the contractor in the base of each caisson. It is suggested that these holes be drilled to a minimum depth of five (5) feet below the base of each foundation. A representative of the soils engineer should use an L-shaped feeler probe to inspect these holes for clay seams, solution cavities, or other voids.

If any soft clay seams or voids are encountered, the caissons should be extended below these unsuitable materials. If clay filled vertical joints or other solution features are encountered, a soils engineer should inspect the rock conditions to determine what measure be required.

Shared Site, L.L.C.
Monticello North 2 Tower
Alt & Witzig File No.: 06CN0072
March 23, 2006
Page 6


Often, because of design and construction details that occur on a project, questions rise concerning the soil conditions. If we can give further service in these matters, please contact us at your convenience.

Respectfully Submitted,

ALT & WITZIG ENGINEERING, INC.

A handwritten signature in black ink, appearing to read "Robert Smith". The signature is fluid and cursive, with a long horizontal stroke at the end.

Robert Smith, P.E.
Project Engineer


A handwritten signature in black ink, appearing to read "Patrick A. Knoll". The signature is cursive and somewhat stylized, with a large initial "P".

Patrick A. Knoll, P.E.

APPENDIX

Boring Location Plan

Monticello North 2 Tower
Monticello, Kentucky



Not To Scale

06CN0072



RECORD OF SUBSURFACE EXPLORATION

Alt & Witzig Engineering, Inc.

CLIENT Boulevard Properties
 PROJECT NAME Monticello North 2 Cell Tower
 LOCATION Monticello, Kentucky

Boring # B-4
 Alt & Witzig File No. 06CN0072

DRILLING and SAMPLING INFORMATION

Date Started 3/17/2006 Hammer Wt. 140 lbs.
 Date Completed 3/17/2006 Hammer Drop 30 in.
 Boring Method HSA Spoon Sampler OD 2 in.

STRATA ELEV.	SOIL CLASSIFICATION	Depth Scale	Strata Depth	Sample No.	Sample Type	Sampler Graphics	Ground Water	Standard Penetration Test, N - Blows/foot	Qu - tsf Unconfined Compressive Strength	Pp - tsf Pocket Penetrometer	Moisture Content %	Remarks
	SURFACE ELEVATION											
	0.0-7" Topsoil											
	7"-8.0 Red Clay Trace Roots and Dolomitized Limestone Fragments	5		1	SS	X		5		2.3	34.5	
				2	SS	X		14		2.5	33.8	
			8.0	3	SS	X		49				
	8.0-9.8 Limestone	10	9.8	4	SS	X		50/3"				
	Auger Refusal at 9.8 feet											

Boring Method
 HSA - Hollow Stem Augers
 CFA - Continuous Flight Auger
 DC - Driving Casing
 MD - Mud Drilling

GROUNDWATER
 ∇ At Completion Dry ft.
 ▼ After hours ft.
 ○ Water on Rods Dry ft.
 C - Boring Caved Depth

Sample Type
 SS - Driven Split Spoon
 ST - Pressed Shelby Tube
 CA - Continuous Flight Auger
 RC - Rock Core
 CU - Cuttings



RECORD OF SUBSURFACE EXPLORATION

Alt & Witzig Engineering, Inc.

CLIENT Boulevard Properties
 PROJECT NAME Monticello North 2 Cell Tower
 LOCATION Monticello, Kentucky

Boring # B-3
 Alt & Witzig File No. 06CN0072

DRILLING and SAMPLING INFORMATION

Date Started 3/16/2006 Hammer Wt. 140 lbs.
 Date Completed 3/16/2006 Hammer Drop 30 in.
 Boring Method HSA Spoon Sampler OD 2 in.

STRATA ELEV.	SOIL CLASSIFICATION	Depth Scale	Strata Depth	Sample No.	Sample Type	Sampler Graphics	Ground Water	Standard Penetration Test, N - Blows/foot	Qu - tsf Unconfined Compressive Strength	Pp - tsf Pocket Penetrometer	Moisture Content %	Remarks
	SURFACE ELEVATION											
	0.0-6" Topsoil											
	6"-9.5 Red Clay with Brown Silt Pocket	5		1	SS	X		9		3.5	33.1	
				2	SS	X		11		4.3	32.0	
				3	SS	X		12	3.9	3.0	30.7	
	9.5-10.5 Dolomitized Limestone	10	9.5 10.5	4	SS	X		26		0.8	37.3	
				5	SS	X		12			55.6	
	10.5-17.5 Red Moist Silty Clay with Dolomitized Limestone Fragments	15		6	SS	X		5			46.4	
				7	SS	X		50/4"			20.2	
	17.5-18.0 Dolomitized Limestone Auger Refusal at 18.0 feet		18.0									

Boring Method
 HSA - Hollow Stem Augers
 CFA - Continuous Flight Auger
 DC - Driving Casing
 MD - Mud Drilling

GROUNDWATER
 ▽ At Completion Dry ft.
 ▽ After hours ft.
 ○ Water on Rods Dry ft.
 C - Boring Caved Depth

Sample Type
 SS - Driven Split Spoon
 ST - Pressed Shelby Tube
 CA - Continuous Flight Auger
 RC - Rock Core
 CU - Cuttings



RECORD OF SUBSURFACE EXPLORATION

Alt & Witzig Engineering, Inc.

CLIENT Boulevard Properties
 PROJECT NAME Monticello North 2 Cell Tower
 LOCATION Monticello, Kentucky

Boring # B-2
 Alt & Witzig File No. 06CN0072

DRILLING and SAMPLING INFORMATION

Date Started 3/16/2006 Hammer Wt. 140 lbs.
 Date Completed 3/16/2006 Hammer Drop 30 in.
 Boring Method HSA Spoon Sampler OD 2 in.

STRATA ELEV.	SOIL CLASSIFICATION	Depth Scale	Strata Depth	Sample No.	Sample Type	Sampler Graphics	Ground Water	Standard Penetration Test, N - Blows/foot	Qu - tsf Unconfined Compressive Strength	Pp - tsf Pocket Penetrometer	Moisture Content %	Remarks
	SURFACE ELEVATION											
	0.0-11" Topsoil											
	11"-4.5 Brown Clay		4.5	1	SS	X		4		1.0	23.9	
	4.5-7.5 Red Moist Clay		7.5	2	SS	X		4		0.3	21.7	
	7.5-14.5 Red Clay		10	3	SS	X		12		4.5	33.6	
	14.5-26.0 Moist Red Silty Clay and Dolomitized Limestone Fragments and Brown Sand Seam		15	4	SS	X		12	6.5	4.5+	28.8	
			14.5	5	SS	X		3			31.2	
			20	6	SS	X		4			35.3	
			20	7	SS	X		4			32.6	
			25	8	SS	X		5		0.3	32.1	
			25	9	SS	X		6			51.1	
	Terminated at 26 feet		26.0									

Boring Method
 HSA - Hollow Stem Augers
 CFA - Continuous Flight Auger
 DC - Driving Casing
 MD - Mud Drilling

GROUNDWATER
 ▽ At Completion Dry ft.
 ▼ After _____ hours _____ ft.
 ○ Water on Rods Dry ft.
 C - Boring Caved Depth

Sample Type
 SS - Driven Split Spoon
 ST - Pressed Shelby Tube
 CA - Continuous Flight Auger
 RC - Rock Core
 CU - Cuttings



RECORD OF SUBSURFACE EXPLORATION

Alt & Witzig Engineering, Inc.

CLIENT Boulevard Properties
 PROJECT NAME Monticello North 2 Cell Tower
 LOCATION Monticello, Kentucky

Boring # B-1
 Alt & Witzig File No. 06CN0072

DRILLING and SAMPLING INFORMATION

Date Started 3/17/2006 Hammer Wt. 140 lbs.
 Date Completed 3/17/2006 Hammer Drop 30 in.
 Boring Method HSA Spoon Sampler OD 2 in.

STRATA ELEV.	SOIL CLASSIFICATION	Depth Scale	Strata Depth	Sample No.	Sample Type	Sampler Graphics	Ground Water	Standard Penetration Test, N - Blows/foot	Qu - tsf Unconfined Compressive Strength	Pp - tsf Pocket Penetrometer	Moisture Content %	Remarks
SURFACE ELEVATION												
	0.0-6" Topsoil											
	6"-10.0 Red Clay	5		1	SS	X		10	4.8	3.5	24.8	
				2	SS	X		13	6.3	4.5+	25.9	
				3	SS	X		12		4.5	25.2	
	10.0-11.0 Red Clay with Dolomitized Limestone											
	11.0-16.0 Rock Core #1 Fissured Dolomite and Limestone REC = 47% RQD = 0%	10	10.0									
			11.0	4	SS	X		20		1.0	40.0	
	16.0-21.0 Rock Core #2 Fissured Dolomite REC = 22% RQD = 0%	16.0										
			21.0									
	Terminated at 21.0 feet											

Boring Method
 HSA - Hollow Stem Augers
 CFA - Continuous Flight Auger
 DC - Driving Casing
 MD - Mud Drilling

GROUNDWATER
 ▽ At Completion Dry ft.
 ▼ After hours ft.
 ○ Water on Rods Dry ft.
 C - Boring Caved Depth

Sample Type
 SS - Driven Split Spoon
 ST - Pressed Shelby Tube
 CA - Continuous Flight Auger
 RC - Rock Core
 CU - Cuttings

GENERAL NOTES

SAMPLE IDENTIFICATION

The Unified Soil Classification System is used to identify the soil unless otherwise noted.

SOIL PROPERTY SYMBOLS

- N: Standard "N" penetration: Blows per foot of a 140 pound hammer falling 30 inches on a 2 inch O.D. split-spoon.
- Qu: Unconfined compressive strength, TSF
- Qp: Penetrometer value, unconfined compressive strength, TSF
- Mc: Water content, %
- LL: Liquid limit, %
- PL: Plastic limit, %
- Dd: Natural dry density, PCF
- : Apparent groundwater level at time noted after completion

DRILLING AND SAMPLING SYMBOLS

- SS: Split-spoon - 1 3/8" I.D., 2" O.D., except where noted
- ST: Shelby tube - 3" O.D., except where noted
- AU: Auger sample
- DB: Diamond bit
- CB: Carbide bit
- WS: Washed sample

RELATIVE DENSITY AND CONSISTENCY CLASSIFICATION

<u>TERM (NON-COHESIVE SOILS)</u>	<u>BLOWS PER FOOT</u>
Very loose	0 - 4
Loose	5 - 10
Firm	11 - 30
Dense	31 - 50
Very Dense	Over 50


<u>TERM (COHESIVE SOILS)</u>	<u>Qu (TSF)</u>
Very soft	0 - 0.25
Soft	0.25 - 0.50
Medium	0.50 - 1.00
Stiff	1.00 - 2.00
Very Stiff	2.00 - 4.00
Hard	4.00+

PARTICLE SIZE

Boulders	8 in.(+)	Coarse Sand	5 mm-0.6 mm	Silt	0.075 mm - 0.005 mm
Cobbles	8 in. - 3 in.	Medium Sand	0.6mm-0.2 mm	Clay	0.005mm(-)
Gravel	3 in. - 5 mm	Fine Sand	0.2mm-0.075 mm		

EXHIBIT K
DIRECTIONS TO WCF SITE

WCF LOCATION MAP



DIRECTIONS TO WCF FROM COUNTY SEAT

From the Wayne County Court House proceed north on Rt. 1275 approximately 1.3 miles. Turn right on Rt. 3106 (Old Highway 90) and proceed approximately 1.2 miles. Site access drive is on the right.

These directions were prepared by:

David B. Jantzi
Boulevard Properties
7383 Utica Boulevard
Lowville, NY 13367
(315) 523-6258

EXHIBIT L

COPY OF REAL ESTATE AGREEMENT

SITE LEASE AGREEMENT

County: Wayne City: Monticello

Site Name: Monticello North Site I. D.: _____ Latitude: 36° 51' 41.28" Longitude: 84° 49' 32.88"

Site Address: Old Highway 90, Monticello, KY 42633

- 1. Premises and Use.** In consideration of the expenditures and efforts of Tenant to develop and use the premises described below, the undersigned (jointly and severally, the "Owner") hereby leases to Shared Sites, LLC, a West Virginia limited liability company ("Tenant"), or its permitted assignee, the site described below:

The exclusive right to use and occupy real property, approximately 10,000 square feet of land, as approximately described and shown on Exhibit A, together with non-exclusive easements (a) to a public right of way, for reasonable access, (b) to the appropriate sources of electric and telephone facilities as determined by Tenant, (c) for placement of any supporting guy wires as reasonably determined by Tenant per good engineering practices and (d) to meet fall-zone or set back requirements (collectively, the "Site"). The Site will be used for installing, maintaining and/or operating, a wireless communications and broadcast facility, including, without limitation, antenna towers or poles, guy wires, foundations, utility lines, equipment shelters, ice bridges, radio equipment, antennas, security alarms, cameras, lights, and supporting equipment thereto (collectively, the "Facility"), or for any other use permitted by applicable law. Title to the Facility shall be held by Tenant and the Facility shall remain Tenant's personal property and in no event shall be construed as fixtures.
- 2. Term.** The term of this Agreement (the "Initial Term") is five (5) years, starting on the date Tenant signs this Agreement. This Agreement will be automatically renewed for ten (10) additional terms (each a "Renewal Term") of five years each with a █% increase in rent at each renewal, unless Tenant provides Owner notice of intention not to renew 90 days prior to the expiration of any term.
- 3. Rent.** Beginning with the date upon which the construction of the Facility is completed, rent will be paid quarterly, on the first day of each calendar quarter, at the rate of \$█ per quarter, partial months to be prorated.
- 4. Title, Quiet Possession, and Access.** Owner represents and agrees (a) that it is the owner of the Site pursuant to the instrument set forth on Exhibit A; (b) that the Site is free from all encumbrances except as set forth on Exhibit A, (c) that it has the right to enter into this Agreement; (d) that the person signing this Agreement has the authority to sign; (e) that Tenant, its employees, agents, subcontractors, clients, and invitees are entitled to access to the Site at all times and to the quiet possession of the so long as Tenant is not in default beyond the expiration of any cure period; and (f) that Owner will not have unsupervised access to the Site or to the related Facility. Owner further represents, agrees and covenants that during the Initial Term and Renewal Terms of this Agreement Owner will not use, or permit others to use, any part of any real property currently owned, or hereafter acquired, by Owner within two (2) miles of the Site for any type of communication or broadcast tower or otherwise provide advice, services for development of competing properties or release any information about Tenant's business. Owner shall obtain non-disturbance, subordination and attornment agreement from prior lien holders as required by Tenant's title insurance company.
- 5. Assignment/Subletting.** Either party may assign or transfer this Agreement with notice to the other party. Upon delivery of such notice the transferor will have no further liability under the Agreement. Tenant shall be allowed to sublet, or otherwise grant use rights to all or any portion of the Site and/or the Facility without the prior written consent of Owner, it being the express intention of Tenant to lease or license antenna, towers, shelters, and related space of the Facility to separate wireless communication carriers and other clients.
- 6. Improvements.** Tenant may make such future improvements on or to the Site and Facility as it deems necessary. Owner agrees to cooperate with Tenant with respect to obtaining any required building/zoning approvals for the Site and improvements. Upon termination or expiration of this Agreement, Tenant shall remove the Facility and its other property located upon the Site, excepting the foundation, and will restore the Site to substantially the condition existing at inception of this lease within 365 days of said termination, except for ordinary wear and tear and casualty loss. Tenant shall reimburse Owner any property tax increases directly attributable to Tenant's improvements. Owner shall fully cooperate Tenant in any available administrative or court appeals of such tax increases.
- 7. Compliance with Laws.** Owner represents that Owner's property (including the Site), and all improvements located thereon, are in substantial compliance with building, life/safety, disability and other laws, codes and regulations of applicable governmental authorities. Tenant will substantially comply with all applicable laws relating to its possession and use.
- 8. Utilities.** Tenant will pay for all utility connections to the Site. Owner will cooperate with Tenant in Tenant's efforts to obtain utilities from the most economical source.
- 9. Termination.** Tenant may terminate this Agreement at any time by notice to Owner without further liability, if Tenant does not obtain all permits or other approvals (collectively, "approval") required from any municipal and/or governmental authority or any easements required from any third party to construct/operate the Facility for its intended use, or if any such approval is canceled, expires or is withdrawn or terminated, or if Owner fails to have proper ownership of the Site or authority to enter into this Agreement, or if Tenant, for any other reason, in its sole discretion, determines that it will be unable to use the Site for its intended purpose.
- 10. Default.** If either party is in default under this Agreement for a period thirty (30) days following receipt of notice from the non-

defaulting party shall have the right to pursue all legal remedies including termination of this Agreement. If a non-monetary default may not reasonably be cured within a thirty (30) day period, this Agreement may not be terminated if the defaulting party commences action to cure the default within such 30 day period and said default is substantially cured within ninety (90) days of the initial notice of default.

11. **Indemnity.** Owner and Tenant each indemnify the other against and hold the other harmless from any and all costs (including reasonable attorneys' fees) and claims of liability or loss which arise out of the use and/or occupancy of the Site or Facility by the direct actions or culpable omissions of the indemnifying party, its employees, agents or independent contractors. This indemnity does not apply to any claims arising from the sole negligence or intentional misconduct or omission of the party seeking indemnification.

12. **Hazardous Substances.** Owner represents that it has no knowledge of any substance, ground contamination, chemical or waste (collectively, "substance") on the Site that is identified as hazardous, toxic or dangerous in any applicable federal, state or local law or regulation. Tenant will not introduce or use any such substance on the Site in violation of any applicable law. Owner shall indemnify Tenant against and hold it harmless from any and all costs (including reasonable attorneys' fees) and claims of liability or loss which arise out of any occurrence or condition causing the presence of any such substance on the Site that occurred prior to the date of this Agreement or is directly attributable to the Owner's use of adjoining premises during the term of this agreement.

13. **Waiver of Owner's Lien.** (a) Owner waives any lien rights it may have concerning the Facility, which is deemed Tenant's personal property and not fixtures, and Tenant has the right to remove the same at any time without Owner's consent. Owner (i) disclaims any interest, now or in the future, in and to the Facility, as fixtures or otherwise; (ii) agrees that the Facility and the leasehold or other use interest of Tenant or its authorized subTenants or users, shall be exempt from execution, foreclosure, sale, levy, attachment, or distress for

any rent due or to become due. and (iii) agrees to provide any lender of the Tenant with an estoppel statement regarding the above facts, such as the lack of a default hereunder, and any other information or document reasonably requested, such as a non-disturbance, subordination and attornment agreement, within five (5) days of request, and shall upon notice by such lender recognize lender as Tenant or execute a new lease on substantially similar terms with such lender.

14. **Insurance.** Tenant, at its sole cost and expense, shall upon commencement of construction (upon use of mechanical equipment to disturb the land, but not for taking of soil samples or surveys and measurements) procure and maintain bodily injury and property insurance on the Facility with a combined single limit of at least One Million Dollars (\$1,000,000). A certificate of such insurance shall be furnished to Owner within 30 days of written request.

15. **Miscellaneous.** (a) This Agreement applies to and binds the heirs, successors, executors, administrators and assigns of the parties to this Agreement; (b) This Agreement is governed by the laws of the State in which the Site is located; (c) This Agreement (including the Exhibits) constitutes the entire agreement between the parties and supersedes all prior agreements; any amendments to this Agreement must be executed by both parties; (e) If any provision of this Agreement is invalid or unenforceable with respect to any party, the remainder of this Agreement, will not be affected and shall remain valid and enforceable to the extent permitted by law; (f) The prevailing party in any action or proceeding in court is entitled to receive its reasonable attorneys' fees and other reasonable enforcement (or, as applicable, defense) costs and expenses; (g) Owner agrees promptly to execute and deliver to Tenant, simultaneously herewith or forthwith hereafter, a recordable Memorandum of this Agreement in the form of Exhibit B; and (h) All notices are effective, on the third business day after their deposit via certified and postage prepaid mail, or, on the next business day after deposit via overnight delivery, to the address below.

"Owner"
 By: _____
 Name: Ronnie Turner
 Title: Owner
 Date: 02-21-2006
 Address: 701 North Main St.
Monticello, KY 42633
 Tax ID: 405-88-7798
 Phone: 606-348-6830

"Owner"

 Jenice Turner
 Owner
 02-21-2006
 701 North Main St.
 Monticello, KY 42633
 404-86-0083
 606-348-6830

Shared Sites, LLC ("Tenant")

 Name: David B. Jantzi
 Site Developer (Subject to Approval)
 Date: 02-21-2006

 Kamal Doshi, Manager (Final Approval)
 Date: _____
 1390 Chain Bridge Road #40
 Mclean, VA 22101 Phone:
 (703)-893-0806

EXHIBIT A
Site Agreement - Site Description – Permitted Exceptions

Site Name: Monticello North


Site I.D.: _____

Site situated in the City/Town of Monticello, County of Wayne, State of Kentucky commonly described as follows:

Legal Description: A portion of the premises located at address: Old highway 90, Monticello, Kentucky 42633

more particularly described in Deed to: Ronnie Turner and Jenice Turner dated May 18th, 2005 and recorded in Wayne County Registry of Deeds at Book 253, Page 548. Tax Map 65, Plot 133.01

Sketch of Site:



Permitted Exceptions: None.

Owner Initials _____ Owner Initials _____ Tenant Initials _____

Note: Owner and Tenant may, at Tenant's option, replace this Exhibit with an exhibit setting forth the legal description of the property on which the Site is located and/or a more detailed survey or drawing depicting the Site.

Prepared by and after recording please return to:
Shared Sites, LLC, 1390 Chain Bridge Road #40, McLean, VA 22101

Tax Map No. 65, Plot No. 133.01

Notice to Clerk: Both Owner and Tenant are to be indexed in the Grantors and Grantees Indices.

Memorandum of Site Lease Agreement

(Exhibit B of the Lease Agreement)

Site Name: Monticello North

Site I.D.: _____

This memorandum evidences that a lease was made and entered into by written Site Lease Agreement dated 02-21-2006, between Ronnie Turner and Jenice Turner ("Owner") and Shared Sites, LLC, a West Virginia limited liability company ("Tenant"), the terms and conditions of which are incorporated herein by reference.

Such Agreement provides in part that Owner leases to Tenant a portion of a certain site ("Site") located at Old Highway 90, City of Monticello, County of Wayne, State of Kentucky owned by Owner, as described in Exhibit A attached hereto, with grant of easement for unrestricted rights of access thereto and to electric, telephone and guy wire facilities for an initial term of five (5) years, which term is subject to ten (10) additional five (5) year extension periods by Tenant.

IN WITNESS WHEREOF, the parties have executed the Memorandum as of the day and year first above written.

"Owner"

"Owner"

"Tenant"
Shared Sites, LLC

By:

Name: Ronnie Turner

Title: Owner

Date: _____

Address: 701 North Main Street

Monticello, KY 42633

Jenice Turner

Owner

701 North Main Street

Monticello, KY 42633

David B. Jantzi

Consultant

1390 Chain Bridge Road #40

McLean, VA 22101

STATE OF _____
CITY/COUNTY OF _____,ss

(Tenant Notary Block)

The foregoing instrument was acknowledged before me this _____ day of _____, 2006, by _____ (Name), _____ (Title) of Shared Sites, LLC, a West Virginia limited liability company (Tenant) on behalf of the limited liability company.

(AFFIX NOTARIAL SEAL)

NOTARY PUBLIC

My commission expires: _____

STATE OF _____
CITY/COUNTY OF _____, ss

(Owner Notary Block for Individuals)

The foregoing instrument was acknowledged before me this _____ day of _____, 2006, by _____ and _____ (Name(s) as applicable), each an Owner.

(AFFIX NOTARIAL SEAL)

NOTARY PUBLIC

My commission expires: _____

STATE OF _____
CITY/COUNTY OF _____,ss

(Owner Notary Block for Companies)

The foregoing instrument was acknowledged before me this _____ day of _____, 2006, by _____ (Name), _____ (Title) of _____ (Owner – Name of Business, N/A if not applicable) a _____ (e.g. A West Virginia Corporation, N/A if not applicable) on behalf of the _____ (Type of Entity- e.g. Corporation, N/A if not applicable).

(AFFIX NOTARIAL SEAL)

NOTARY PUBLIC

My commission expires: _____

EXHIBIT M
FLOOD PLAIN CERTIFICATION

.....

McKinney Land Surveying
103 South Reed Street
Columbia KY, 42728

McKinney Land Surveying


June 7, 2006

To Whom It May Concern:

The "Monticello North" site located in Wayne County, Kentucky {Proposed for lease by Shared Sites L.L.C., for the purpose of erecting a telecommunications tower} is classified as **Zone D**. This classification is zoning for a nonparticipating community. For more information on this zoning description, please refer to *The United States Department of Housing and Urban Authority-Federal Insurance Administration*.

Respectfully,

Michael E. McKinney 06/07/06
Michael E. McKinney
P.L.S. #3318



.....

EXHIBIT N
NOTIFICATION LISTING

CERTIFICATION OF NOTIFICATION

- 1) Thomas E. and Bruce Carroll
51 Court St.
Monticello, KY 42633
- 2) Bruce and Winna Ramsey
64 Sloan Drive
Monticello, KY 42633
- 3) James Lynn and Sue Jones
1080 Old Highway 90
Monticello, KY 42633
- 4) Ronnie and Jenice Turner
701 North Main Street
Monticello, KY 42633
- 5) The Honorable Bruce Ramsey
Wayne County Judge Executive
PO Box 257
Monticello KY 42633
- 6) Thurston Frye
City of Monticello Mayor
Post Office Box 566
157 S Main St
Monticello, KY 42633

EXHIBIT O

COPY OF PROPERTY OWNER NOTIFICATION

David B. Jantzi
Shared Sites, LLC
1390 Chain Bridge Rd. #40
McLean, VA 22101

Tuesday, April 11, 2006

Thomas E. and Bruce Carroll
51 Court Street
Monticello, KY 42633

RE: Public Notice – Kentucky Public Service Commission
Docket # 2006-00110

Dear Sir or Madam:

Shared Sites, LLC and American Cellular Corporation are making application to the Kentucky Public Service Commission (PSC) for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide wireless communication services. The facility will include a 195-foot tower with appurtenances attached to a maximum height of 199 feet, and a ground level equipment shelter(s) to be located at 1080 Old Highway 90, Monticello, KY 42633. This notice is being sent to you because you own property within a 500' radius of the proposed tower or have property adjoining the property where the tower is proposed.

The Kentucky Public Service Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. Your initial communication to the PSC must be received by the PSC within 20 days of the date of the Postal cancellation on the envelope this letter was received in. Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, 211 Sower Boulevard, Post Office Box 615, Frankfort, KY 40602-0615. Please refer to Docket No.: 2006-00110 in your correspondence.

Please feel free to contact David Jantzi at 315-376-3333, if you have any questions.

Sincerely,
Shared Towers KY, LLC



David B. Jantzi
Consultant

David B. Jantzi
Shared Sites, LLC
1390 Chain Bridge Rd. #40
McLean, VA 22101

Tuesday, April 11, 2006

Bruce and Winna Ramsey
64 Sloan Drive
Monticello, KY 42633

RE: Public Notice – Kentucky Public Service Commission
Docket # 2006-00110

Dear Sir or Madam:

Shared Sites, LLC and American Cellular Corporation are making application to the Kentucky Public Service Commission (PSC) for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide wireless communication services. The facility will include a 195-foot tower with appurtenances attached to a maximum height of 199 feet, and a ground level equipment shelter(s) to be located at 1080 Old Highway 90, Monticello, KY 42633. This notice is being sent to you because you own property within a 500' radius of the proposed tower or have property adjoining the property where the tower is proposed.

The Kentucky Public Service Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. Your initial communication to the PSC must be received by the PSC within 20 days of the date of the Postal cancellation on the envelope this letter was received in. Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, 211 Sower Boulevard, Post Office Box 615, Frankfort, KY 40602-0615. Please refer to Docket No.: 2006-00110 in your correspondence.

Please feel free to contact David Jantzi at 315-376-3333, if you have any questions.

Sincerely,
Shared Towers KY, LLC



David B. Jantzi
Consultant

David B. Jantzi
Shared Sites, LLC
1390 Chain Bridge Rd. #40
McLean, VA 22101

Tuesday, April 11, 2006

James Lynn and Sue Jones
1080 Old Highway 90
Monticello, KY 42633

RE: Public Notice – Kentucky Public Service Commission
Docket # 2006-00110

Dear Sir or Madam:

Shared Sites, LLC and American Cellular Corporation are making application to the Kentucky Public Service Commission (PSC) for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide wireless communication services. The facility will include a 195-foot tower with appurtenances attached to a maximum height of 199 feet, and a ground level equipment shelter(s) to be located at 1080 Old Highway 90, Monticello, KY 42633. This notice is being sent to you because you own property within a 500' radius of the proposed tower or have property adjoining the property where the tower is proposed.

The Kentucky Public Service Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. Your initial communication to the PSC must be received by the PSC within 20 days of the date of the Postal cancellation on the envelope this letter was received in. Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, 211 Sower Boulevard, Post Office Box 615, Frankfort, KY 40602-0615. Please refer to Docket No.: 2006-00110 in your correspondence.

Please feel free to contact David Jantzi at 315-376-3333, if you have any questions.

Sincerely,
Shared Towers KY, LLC



David B. Jantzi
Consultant

David B. Jantzi
Shared Sites, LLC
1390 Chain Bridge Rd. #40
McLean, VA 22101

Tuesday, April 11, 2006

Ronnie and Jenice Turner
701 North Main Street
Monticello, KY 42633

RE: Public Notice – Kentucky Public Service Commission
Docket # 2006-00110

Dear Sir or Madam:

Shared Sites, LLC and American Cellular Corporation are making application to the Kentucky Public Service Commission (PSC) for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide wireless communication services. The facility will include a 195-foot tower with appurtenances attached to a maximum height of 199 feet, and a ground level equipment shelter(s) to be located at 1080 Old Highway 90, Monticello, KY 42633. This notice is being sent to you because you own property within a 500' radius of the proposed tower or have property adjoining the property where the tower is proposed.

The Kentucky Public Service Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. Your initial communication to the PSC must be received by the PSC within 20 days of the date of the Postal cancellation on the envelope this letter was received in. Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, 211 Sower Boulevard, Post Office Box 615, Frankfort, KY 40602-0615. Please refer to Docket No.: 2006-00110 in your correspondence.

Please feel free to contact David Jantzi at 315-376-3333, if you have any questions.

Sincerely,
Shared Towers KY, LLC



David B. Jantzi
Consultant

EXHIBIT P

COPY OF JUDGE EXECUTIVE NOTICE

David B. Jantzi
Shared Sites, LLC
1390 Chain Bridge Rd. #40
McLean, VA 22101

Tuesday, April 11, 2006

The Honorable Bruce Ramsey
Wayne County Judge Executive
PO Box 257
Monticello, KY 42633

RE: Public Notice – Kentucky Public Service Commission
Docket # 2006-00110

Dear Sir or Madam:

Shared Sites, LLC and American Cellular Corporation are making application to the Kentucky Public Service Commission (PSC) for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide wireless communication services. The facility will include a 195-foot tower with appurtenances attached to a maximum height of 199 feet, and a ground level equipment shelter(s) to be located at 1080 Old Highway 90, Monticello, KY 42633. This notice is being sent to you because you are the Wayne County Judge Executive

The Kentucky Public Service Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. Your initial communication to the PSC must be received by the PSC within 20 days of the date of the Postal cancellation on the envelope this letter was received in. Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, 211 Sower Boulevard, Post Office Box 615, Frankfort, KY 40602-0615. Please refer to Docket No.: 2006-00110 in your correspondence.

Please feel free to contact David Jantzi at 315-376-3333, if you have any questions.

Sincerely,
Shared Towers KY, LLC



David B. Jantzi
Consultant

David B. Jantzi
Shared Sites, LLC
1390 Chain Bridge Rd. #40
McLean, VA 22101

Tuesday, April 11, 2006

Thurston Frye
City of Monticello Mayor
PO Box 566
Monticello, KY 42633

RE: Public Notice -- Kentucky Public Service Commission
Docket # 2006-00110

Dear Sir or Madam:

Shared Sites, LLC and American Cellular Corporation are making application to the Kentucky Public Service Commission (PSC) for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide wireless communication services. The facility will include a 195-foot tower with appurtenances attached to a maximum height of 199 feet, and a ground level equipment shelter(s) to be located at 1080 Old Highway 90, Monticello, KY 42633. This notice is being sent to you because you are the Mayor of the City of Monticello.

The Kentucky Public Service Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. Your initial communication to the PSC must be received by the PSC within 20 days of the date of the Postal cancellation on the envelope this letter was received in. Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, 211 Sower Boulevard, Post Office Box 615, Frankfort, KY 40602-0615. Please refer to Docket No.: 2006-00110 in your correspondence.

Please feel free to contact David Jantzi at 315-376-3333, if you have any questions.

Sincerely,
Shared Towers KY, LLC



David B. Jantzi
Consultant

EXHIBIT Q
COPY OF POSTING NOTICES

**SHARED SITES, L.L.C PROPOSES
TO CONSTRUCT A TELECOMMUNICATIONS
TOWER NEAR THIS SITE**

IF YOU HAVE QUESTIONS PLEASE CONTACT

David Jantzi (Shared Sites Representative)

1390 Chain Bridge Rd. #40, McLean, VA 22101

315-523-6258

OR

Executive Director, Public Service Commission

211 Sower Boulevard

PO Box 615, Frankfort, KY 40602

Docket# 2006-00110

**SHARED SITES, L.L.C PROPOSES
TO CONSTRUCT A TELECOMMUNICATIONS
TOWER ON THIS SITE**

IF YOU HAVE QUESTIONS PLEASE CONTACT

David Jantzi (Shared Towers Representative)

1390 Chain Bridge Rd. #40, McLean, VA 22101

315-523-6258

OR

Executive Director, Public Service Commission

211 Sower Boulevard

PO Box 615, Frankfort, KY 40602

Docket# 2006-00110

EXHIBIT R

RADIO FREQUENCY DESIGN SEARCH AREA

RADIO FREQUENCY DESIGN SEARCH AREA





EXHIBIT S


TOWER MAP FOR SUBJECT COUNTY

MAP OF EXISTING TOWERS FOR WAYNE COUNTY



DELORME

Data use subject to license
 © 2004 DeLorme, Topo USA® 5.0
 www.delorme.com



1	<u>1004214</u>	Constructed	A0103300	Cumberland Cellular Partnership	36-48-34.0N 084-50-46.0W	MONTICELLO, KY	200.00
2	<u>1008398</u>	Constructed	A0009993	STAPLES JR, STEPHEN W DBA = WKYM FM	36-48-36.0N 084-50-49.0W	MONTICELLO, KY	200.00
3	<u>1042205</u>	Constructed	A0455314	Global Tower, LLC	36-53-48.0N 084-59-32.0W	PARNELL, KY	420.00
4	<u>1043628</u>	Constructed	A0051337	CELLULAR PHONE OF KENTUCKY, INC. DBA = RAMCELL	36-58-25.0N 084-39-09.0W	BURNSIDE, KY	195.00
5	<u>1043974</u>	Constructed	A0318927	Monticello Wayne County Telecommunications Board	36-48-58.0N 084-51-07.0W	MONTICELLO, KY	200.00
6	<u>1044810</u>	Constructed	A0052862	KY EMERGENCY WARNING SYSTEM KEWS	36-50-40.0N 084-46-27.0W	PARKERS LAKE, KY	275.00
7	<u>1059114</u>	Constructed	A0361877	STAPLES JR, STEPHEN W DBA = WFLW AM	36-50-14.3N 084-51-49.8W	MONTICELLO, KY	185.00
8	<u>1065830</u>	Constructed	A0151378	MONTICELLO WAYNE COUNTY MEDIA INC DBA = WMKZ FM	36-48-29.0N 084-50-46.0W	MONTICELLO, KY	18.00
9	<u>1200492</u>	Constructed	A0134682	Cumberland Cellular Partnership	36-53-50.0N 084-57-27.0W	Monticello, KY	420.00
10	<u>1203422</u>	Constructed	A0455388	Global Tower, LLC	36-57-06.3N 084-49-13.8W	Monticello, KY	300.00
11	<u>1204639</u>	Granted	A0099865	Commercial Communications Co	36-48-25.2N 084-50-44.8W	Monticello, KY	112.00
12	<u>1235686</u>	Granted	A0280520	MONTICELLO, CITY OF	36-48-25.5N 084-50-38.1W	MONTICELLO, KY	178.00
13	<u>1238700</u>	Constructed	A0327782	Hemphill Corporation - 1366	36-53-52.1N 084-47-02.5W	Monticello, KY	320.00